

2-070693

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

5-1 15-155-01494-00-01
DOCKET # ~~B-23,208~~
API NUMBER: 15- *KcepB*

NE SE SW, SECTION 21 TOWNSHIP 23 RANGE 10W

OPERATOR LICENSE # 30364 990 FEET FROM S SECTION LINE
OPERATOR RESOURCE OPERATIONS INC 2970 FEET FROM E SECTION LINE
NAME & BOX 466 #2
ADDRESS CHASE, KS 67524
LEASE NAME: KREIE
COUNTY: RENO
WELL TOTAL DEPTH: 3788' 123.11
PIPE: 5 1/2" @ 3765'
SURFACE CASING: 8 5/8" @ 240'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD ~~SWD~~ D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 1 MONTH: 5 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: 1900' - 35 SACKS
1450' - 35 SACKS
700' - 35 SACKS
300' - 0'

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART NONE

COMPLETED: HOUR: 5:00PM DAY: 1 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: SHOT PIPE OFF AT 1450', DIDN'T GET LOOSE. RAN TUBING IN TO 1922', TAGGED OUT, PUMPED 35 SACKS. PULLED TO 1450, PUMPED 35 SACKS. PULLED TUBING. SHOT 5 1/2" CASING OFF AT 1100'. PULLED TO 700', PUMPED 35 SACKS. PULLED TO 300', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #5534

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

JUN 05 1997

CONSERVATION DIVISION
WICHITA, KS

6-5-97

INVOICED

JUN 06 1997

DATE
INV. NO. 48258

FORM CP-2/3

REV. 3/90