

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 207B  
Wichita, Kansas 67202

12-11

API NUMBER: 15-155-21432-000

SE-SE-SW, SECTION 25 TOWNSHIP 23S RANGE 10W

OPERATOR LICENSE # 5058  
OPERATOR Griqqs Oil Inc.  
NAME & 209 E. William Suite #220  
ADDRESS Wichita, KS 67202

330 FEET FROM S SECTION LINE  
2970 FEET FROM E SECTION LINE

LEASE NAME: Geist # 1-25  
COUNTY: Reno  
WELL TOTAL DEPTH: 3730' *121.23*  
PIPE: \_\_\_\_\_  
SURFACE CASING: 8 5/8" @ 218'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION  
1-11-99

PLUGGING CONTRACTOR: Sterling Drilling Co.  
ADDRESS: P.O. Box 1006 Pratt, KS 67124 LICENSE: 5142

JAN 11 1999

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 11 MONTH: 12 YR: 1998 CONSERVATION DIVISION WICHITA, KS

PLUGGING PROPOSAL RECEIVED FROM: Vaughn Thompson

COMPANY NAME: Sterling Drilling Co. PHONE: 316-672-9508

WERE: Fill hole with heavy mud and spot cement through drill pipe.  
Spot thirty-five sacks cement at 1400', thirty-five sacks cement at  
900', thirty-five sacks cement at 270', twenty-five sacks cement at  
60', fifteen sacks cement in the rathole, and ten sacks cement in  
the mouse hole.

PLUGGING PROPOSAL RECEIVED BY: Butch Hoberecht

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (\_\_\_\_\_) PART (\_\_\_\_\_) NONE ( X )

COMPLETED: HOUR: 12:00 DAY: 11 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT: Filled hole with heavy mud. Spotted cement through  
drill pipe. Spotted thirty-five sacks cement at 1400', thirty-five  
sacks cement at 900', thirty-five sacks cement at 270', 25 sacks  
cement at 60', fifteen sacks cement in the rathole, and ten sakcs  
cement in the mouse hole.

REMARKS: Used 60/40 pos mix with 4% gel by Allied. Invoice # 2556

I DID NOT OBSERVE THIS PLUGGING.

*Michael R. Wilson*  
Michael R. Wilson

1-15-99  
60554