

1 060496

15.083.21143.00.00 R
API NUMBER 15- not available

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW , SEC. 14 , T 21 S, R 21 W/K

330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License #6050

Lease Name Rodney Well # 1

Operator: Kelso Casing Pulling

County Hodgeman

Name & Address Box 347

Well Total Depth 4370 142.03 feet

Chase, KS 67524

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1291

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 27 Month: February Year: 19 85

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4368' PBDT 4323' Perfs from 4316-22'

1st plug sand back to 4265' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 27 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4265' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

3-4-85 MAR 04 1985

Maximum pressure 1500 psi and shut in 800 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Recovered 2850' 5 1/2" casing, Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did ~~not~~) observe this plugging.

DATE 3-7-85

Signed Paul A. Luthi (TECHNICIAN)

INSTR. NO. 7243