

1 060966

6-17-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,030A

C N/2 NE, SEC. 11, T 22 S, R 15 W/E

4620 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Lease Name Crane (OWWO) Well # 1

Operator: Grady Bolding, Corp.

County Pawnee 128.47

Name & Address Box 244

Well Total Depth 3953 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 932

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 17 Month: 6 Year: 1987

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-793-6496

were: 4 1/2" at 3953' BPTD 3922' Perfs at 3224-27'

1st plug sand back to 3175' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 'sx hulls and 125 sx econolite.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 17 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3175' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1987

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 850 psi and shut in 650 psi.

Remarks: Used ATL by Halliburton. Recovered 2000' of 4 1/2" casing. 6-19-87
(If additional description is necessary, use BACK of this form.)

INVOICED (observe this plugging.)

Signed Paul A. Luthie
(TECHNICIAN)

DATE 6-22-87

INV. NO. 17285

6-17