

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,030-0000

NE 1/4, Sec. 11, T 22 S, R 15 W/K  
660 feet from N/S section line  
1320 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8399

Lease Name Crane Well # 1

Operator: Great Bend Oil Producers  
Name & P.O. Box 1054  
Address Great Bend, KS 67530

County PAWNEE

Well Total Depth 3951 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 932

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 9:00 a.m. Day: 28 Month: April Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Greg Davidson

(company name) Allen Drilling (phone) \_\_\_\_\_

were: to use 50/50 Pozmix w/ 4% gel & 3% CaCl and locate the first plug @ 990 feet  
w/40 sx; 2nd plug @ 420 feet w/ 40 sx. ; 3rd plug @ 40 feet w/ solid bridge  
of hulls and 8 5/8 wiper plug; 4th plug 40 feet to surface w/ 10 sx. Circulate  
15 sx in the rathole.

Signed Robert Barkhutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:40 a.m. Day: 28 Month: April Year: 19 83

ACTUAL PLUGGING REPORT Well plugged as ordered. Cementing by Allied Cementing.

Remarks: Elevation 1965 G.L.---8 5/8 cemented w/ 375 sx. of 60/40 Pozmix, 2% gel-  
3% CaCl--

Anhydrite top @ 923 ft.

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / ~~did not~~) observe this plugging.

INVOICED RECEIVED  
STATE CORPORATION COMMISSION

DATE 5-6-83

INV. NO. 4210-W MAY 03 1983

CONSERVATION DIVISION  
Wichita, Kansas

Signed Robert Barkhutton  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82