


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pawnee County. Sec. 11 Twp. 22 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines SW SE SW
Lease Owner Natural Gas and Oil Corporation
Lease Name Wesley Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed January 19, 1954 19
Application for plugging filed January 20, 1954 (Orally) 19
Application for plugging approved January 21, 1954-written 19
Plugging commenced January 20, 1954 19
Plugging completed January 20, 1954 19
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface		0	204	8 5/8"	203	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 4016 to 200 feet
Set plug at 200 feet and ran 20 sacks cement to 140 feet
Filled with heavy mud from 140 to 40 feet
Set plug at 40 feet and ran 10 sacks cement to cellar

1-26-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Drilling Department of Natural Gas and Oil Corporation
Address 1009 Central Building, Wichita 2, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Harold A. Burt, Regional Manager (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold A. Burt
1009 Central Building, Wichita, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 54

Esther Unsell
Esther Unsell Notary Public.

My commission expires May 25, 1957



DRILLER'S LOG

COMPANY: Natural Gas and Oil Corporation
 CONTRACTOR: Drilling Dept-Natural Gas & Oil Corp
 FARM: Wesley #1, SW SE SW 11-22-15W
 Pawnee County, Kansas
 COMMENCED: January 7, 1954
 COMPLETED: January 20, 1954
 ELEVATION: 1978

0	to	15	Clay
15	to	115	Sand
115	to	204	Shale and shells
204	to	225	Shale
225	to	270	Sand
270	to	405	Shale, red bed and shells
405	to	475	D. sand
475	to	530	Shale and red bed
530	to	933	Red bed
933	to	958	Anhydrite
958	to	1350	Shale and shells
1350	to	1585	Salt, shale and shells
1585	to	1800	Shale and lime
1800	to	1945	Lime
1945	to	2075	Lime-some chert
2075	to	2155	Lime
2155	to	3075	Lime and shale
3075	to	3138	Lime
3138	to	3165	Sandy lime
3165	to	3183	Lime
3183	to	3346	Lime and shale
3346	to	3398	Lime
3398	to	3526	Lime and shale
3526	to	3729	Lime
3729	to	3843	Lime and shale
3843	to	3868	Conglomerate
3868	to	3902	Lime and chert
3902	to	3948	Shale
3948	to	3980	Simpson
3980	to	4016	Arbuckle lime
		4016	T. D.

Set 203 feet of 8 5/8" 25# surface pipe. Cemented with 200 sacks cement and 4 sacks calcium chloride

TOPS: Anhydrite	933	Lansing	3519	Simpson	3932
Heebner	3393	Base KC	3745	Arbuckle	3980
Brown Ls	3506	Viola	3850		

DST: #1 3521-54, open 1 hr SI 15 min, rec. 1260' muddy water, 60' SOCW, IFP 380#, FFP 680#, BHP 1400#.

#2 3635-50, op 1 hr, SI 20 min, weak blow, 20' OCM, BHP 125#.

#3 3653-88, op 1 hr, SI 15 min, 510' muddy salt water, FFP 280#, BHP 1070#.

#4 3854-3905, op 1 hr, SI 15 min, 25' oil spkd mud, wk blow 25 min, no pressured.

No Schlumberger

DRY, PLUGGED AND ABANDONED

c e r t i f i c a t e

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of the log of the Wesley #1, SW SE SW Section 11-22S-15W, Pawnee County, Kansas, as reflected by files of the Natural Gas and Oil Corporation.

Harold A. Burt

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 25th day of January, 1954.

My commission expires May 25, 1957 Esther Unsell, Notary Public

RECEIVED

PLUGGING

FILE SEC 11 T 22 R 15W
 BOOK PAGE 9 LINE 21