


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Location as "NE/CNW/SW" or footage from lines Pawnee County, Sec. 11 Twp. 22S Rge. (E) 15 (W) (W)  
Lease Owner F & M Oil Co.  
Lease Name Branstetter Well No. 1  
Office Address 603 Union Center - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 4-9 19 71  
Application for plugging filed 4-9 19 71  
Application for plugging approved 4-9 19 71  
Plugging commenced 2:30 PM 4-9- 19 71  
Plugging completed 3:30 Pm 4-9 19 71  
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 8958 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	300	8 5/8"	298	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

50 sx thru drill pipe @ 450' 25 sx @ 270' 10 sx @ 40'  
2 sx in rat hole - plugged by Halliburton & Leo Massey

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor B & B Drilling, Inc.  
Address 720 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar  
720 Union Center - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 71

My commission expires May 31, 1971  
Alma A. Norris Notary Public.

**B & B DRILLING, INC.**207 Petroleum Building  
Wichita, Kansas 67202

April 13, 1971

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1971  
CONSERVATION DIVISION  
Wichita, KansasDRILLERS LOGRe: Branstetter #1  
NE NW NW Section 11-22S-15W  
Pawnee County, Kansas

OPERATOR: F & M Oil Co.  
 CONTRACTOR: B & B Drilling, Inc.  
 COMMENCED: March 31, 1971  
 COMPLETED: April 9, 1971  
 TOTAL DEPTH: 3958'

Ran 3 5/8" @ 298 w/250 sx

0	300	Surface	
300	840	Shale & Red Bed	
840	928	Shale	
928	953	Anhydrite	
953	1322	Shale	
1322	1983	Shale	
1983	2275	Lime & Shale	
2275	3015	Shale & Lime	
3015	3105	Lime & Shale	
3105	3590	Lime	DST #1 3505 - 3590'
3590	3621	Lime & Shale	DST #2 3915 - 3945'
3621	3688	Lime	DST #3 3946 - 3958'
3688	3737	Lime	
3737	3915	Lime	
3915q	3958	Lime	
3958		Total Depth	D & A

We certify the above and foregoing to be true and correct copy of the log on the #1 Branstetter located in Pawnee County, Kansas.

Bill Lahan President

Alma G. Neuser Notary Public

Subscribed and sworn to before me this 13th day of April, 1971. My commission expires May 31, 1974.