


STATE OF KANSAS  
STATE-CORPORATION COMMISSIONGive All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH

Locate well correctly on above  
Section Plat

Stafford County, Sec. 17 Twp. 22S Rge. (E) 14 (W)  
 Location as "NE/CNW/SW" or footage from lines NW NE SW  
 Lease Owner Chief Drilling Co. & Hudson Petroleum  
 Lease Name Carr Well No. 1  
 Office Address P. O. Box 97 - Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed January 4 1958  
 Application for plugging filed January 5 1958  
 Application for plugging approved 19  
 Plugging commenced 3:30 P.M. January 4 1958  
 Plugging completed 6:00 P.M. January 4 1958  
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kans.  
 Producing formation Depth to top Bottom Total Depth of Well 3890 Feet  
 Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	299'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1/3 sack Halls, wooden plug at 240'. Mixed 20 sacks cement through drill pipe.

1/3 sack Halls, wooden plug at 30', with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas, COUNTY OF Barton, ss.  
 V. Richard Hoover (Employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Chief Drilling Co., Inc. - Box 97 - Great Bend,  
 (Address) Kansas

SUBSCRIBED AND SWORN TO before me this 5th day of January, 1959

My commission expires November 21, 1959



WELL LOG

No. 1 Carr

Chief Drilling & Hudson Petroleum  
P. O. Box 97  
Great Bend, Kansas

No. 1 Carr  
NW NE SW Sec. 17-22S-14W  
Stafford County, Kansas

Commenced: December 23, 1958  
Completed: January 4, 1959

DRY AND ABANDONED

Contractor: Chief Drilling Co., Inc.  
Rotary: 0-3980' T.D.

Casing Record: 8-5/8" surface casing set at 300' with 275 Pozmix Cement, 2% Calcium Chloride. Cement circulated.

Figures Indicate Bottoms of Formations

Surface Sand and Gravel	0 - 299
Shale and Shells	299 - 375
Sand	375 - 405
Shale, Shells, Red Bed	405 - 872
Anhydrite	872 - 895
Shale and Shells	895 - 1710
Lime and Shale	1710 - 1915
Lime	1915 - 2020
Lime and Shale	2020 - 3195
Lime	3195 - 3890 T.D.

State of Kansas )  
County of Barton )

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the NW NE SW of Section 17, Township 22 South, Range 14 West, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 6th day of January, 1959.

*Mary O. Johnson*  
Mary O. Johnson, Notary Public

My Commission Expires:  
November 21, 1959

**RECEIVED**  
CORPORATION COMMISSION  
JAN 12 1959  
DIVISION  
Kansas

**PLUGGING**  
FILE SEC 17 T 22 R 14W  
BOOK PAGE 10 LINE 19