

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 33 TWP. 22 RGE. 14 X/W
Location as in quarters or footage from lines:
NE/SW/SE

Lease Owner Brougner Oil, Inc.
Lease Name Miller; "B" Well No. #1
Office Address Box 1367 - Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed _____
Application for plugging filed _____
Plugging commenced January 11, 1983
Plugging completed January 25, 1983
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3663'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	236'	NONE
				4 1/2"	4003'	3039.84'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Dumped sand to 3875' and four (4) sacks cement.
Shot pipe @ 3400', 3000' and 2800'.
Pulled ninety-four (94) joints 4 1/2" casing.
Squeezed well with three (3) sacks hulls, fifty (50) sacks
cement, thirty (30) sacks gel, one (1) sack hulls,
one hundred twenty (120) sacks 50/50 pozmix cement with 4%
added gel and 3% calcium chloride. Max. press. 500 p.s.i.
and shut in at 500 lbs. p.s.i. Completed at 12:15 p.m.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
JAMES W. ROCKHOLD / Box 698 - Great Bend, Ks.
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 31st day of February, 1983



My Commission expires _____

Margaret Prosser
Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1983