

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 33 Twp. 22 Rge. 14 (E) (W) X

Location as "NE/CNW%SW%" or footage from lines SE SE SW

Lease Owner Forbes Casing Pulling, Inc.

Lease Name Wood Well No. 1

Office Address P. O. Box 221 Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 1-23-69 19

Application for plugging approved 1-24-69 19


Plugging commenced 1-25-69 19

Plugging completed 2-9-69 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation Depth to top Bottom Total Depth of Well 11019 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	245	None
				5 1/2	None	2415
RECEIVED STATE CORPORATION COMMISSION FEB 11 1969 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 3850'. Dumped 5 sacks of cement. Working pipe. Shot pipe at 2950'.

Working pipe. Shot pipe at 2860'.

Circulating. Spotted 60 bbl. of oil. Working pipe. Shot pipe at 2700' - 2600' - 2500' and 2420'. Pulling pipe.

Cleaned out cellar. Shut in water. Plugged well. Squeezed with 10 sacks of mud and 75 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9 day of February, 19 69

My commission expires May 27, 1969

Notary Public.

15.185.20061.0000 ✓

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY - L. R. Birkholz


SEC. 33 T. 22 R. 14W
LOC. SE SE SW

FARM Wood NO. 1

COUNTY Stafford

TOTAL DEPTH 4022'
COMM. Oct. 16 '67 COMP. Oct. 25 '67

SHOT OR TREATED
CONTRACTOR Woodman & Iannitti Drilling Company
ISSUED 2-17-68



CASING
20 10
15 8 X 2 1/2" 254' cem w/ 200 sx
12 6
13 5 4019'

ELEVATION 1955' KB

PRODUCTION 20 BOPD P 135 8 1/2 W
Simp 3930-43

FIGURES INDICATE BOTTOM OF FORMATIONS

140	Sand	TOPS: LOG	
180	Blue Shale	Keebner	3388
320	Shale	Toronto	3409
400	Sand	Douglas	3427
860	Red Bed	Brown Lime	3518
895	Anhy	Lansing	3530
970	Shale	Base Kansas City	3760
1070	Shale	Viola	3858
1270	Shells	Simpson shale	3910
1620	Shale & Shells	Simpson sand	3930
1875	Shale & Lime	Arbuckle	3970
2025	Lime	RTD	4020
2180	Lime	LTD	4022
2365	Lime & Shale		
2560	Lime & Shale		
2760	Lime & Shale		
2920	Lime & Shale		
3060	Lime		
3210	Lime		
3300	Lime		
3365	Lime		
3515	Lime		
3562	Lime		
3560	Lime		
3660	Lime		
3675	Lime		
3755	Lime		
3840	Lime		
3890	Lime & Chert		
3940	Chert & Lime		
3950	Lime		
4020	Lime RTD		
4022	LTD		

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Company

K. T. Woodman