

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 19 Twp 22S Rge. 14 XXX (W)

Location as "NE/CNW¼SW¼" or footage from lines NW NW NE
Lease Owner Anschutz Drilling Company, Inc.

Lease Name Carr Well No. 1

Office Address 709 Union National Bank Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed. 8/8 1950

Application for plugging filed..... 8/8 1950

Application for plugging approved.....8/8.....1850

Plugging commenced 8/8 1950

Plugging completed.....8/8.....1950

Reason for abandonment of well or producing formation...Dry.....

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....C. D. Stough

Producing formation..... Depth to top..... Bottom..... Total Depth of Well.....4033 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Bottom plug set at 260' with 15 sacks cement.

Top plug set at 30' with 10 sacks cement.

RECEIVED

~~AUG 12 1950~~

8-12-50

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Anschutz Drilling Company, Inc.
Address: 709 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. W. Smith (employee of owner) or (owner or operator) of the above-described well

.....M. W. Smith.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God. *[Signature]*

(Signature).....

709 Union National Bank, Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 11th day of August 1950

My commission expires January 21, 1954 Patricia Meeker Notary Public.

28-8278-g 4-50-10M

25-0210-8

PLUGGING

FILE NO. 197Y2A 190

DATE MAY 20 1967

Anschutz Drilling Company, Inc.
DRILLER'S LOG

#1 Carr.
NW NW NE - Section 19-22S-14W
Stafford County, Kansas

0	135	Sand
135	280	Shale & shells
280	313	Shale
313	465	Shale red bed
465	890	Red rock & sand
890	920	Anhydrite
920	960	Shale & shells
960	1210	Shale & shells
1210	1280	Salt & shale & shells
1280	1505	Shale & broken lime
1505	1695	Shale & shells
1695	1750	Lime & shale
1750	1875	Lime & shale
1875	2020	Shale lime & shells
2020	2040	Shale & shells
2040	2125	Lime
2125	2225	Lime & shale
2225	2320	Lime & shale
2320	2445	Lime & shale
2445	2595	Shale & lime
2595	2730	Shale & lime
2730	2850	Shale & shells
2850	2910	Lime
2910	3045	Lime & shale
3045	3135	Lime & shale
3135	3220	Lime
3220	3320	Lime
3320	3395	Lime
3395	3435	Lime
3435	3515	Shale & lime streaks
3515	3525	Lime
3525	3573	Lime
3573	3617	Lime
3617	3665	Lime
3665	3720	Lime
3720	3755	Lime
3755	3820	Shale & lime
3820	3860	Conglomerate
3860	3867	Lime & shale
3867	3885	Lime & chert
3885	3895	Chert
3895	3920	Lime & chert
3920	3980	Lime, chert & shale
3980	3998	Conglomerate
3998	4033	Arbuckle
4033		ROTARY TOTAL DEPTH

COMMENCED: 7/25/50
COMPLETED: 8/8/50

CASING RECORD:

Set 8-5/8" surface casing
@ 260' w/250 sacks cement.

STATE OF KANSAS

COUNTY OF SEDGWICK


I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Carr, located in the NW NW NE of Section 19-22S-14W, Stafford County, Kansas.

ANSCHUTZ DRILLING CO., INC.

BY:

M. W. Smith

Subscribed and sworn to before me this 11th day of August, 1950.



My commission expires January 21, 1954.

Notary Public