


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 32 Twp. 22 Rge. 14 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NW SE
Lease Owner Big "J" Prod. Co., & Quadel Energy Corp.
Lease Name STANDISH Well No. 1
Office Address 427 North St. Francis, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole



Locate well correctly on above
Section Plot

Date Well completed 10/24 1981
Application for plugging filed 10/24 1981
Application for plugging approved 10/24/1981
Plugging commenced 10/24 1981
Plugging completed 10/24 1981
Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation Depth to top Bottom Total Depth of Well 4215'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	316'	8-5/8"	316'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

60 sks @ 630'
40 sks @ 300'
10 sks @ 40'
10 sks rathole
50/50 poz., 2% gel, 3% cc., by Sun
plug down 4:30 PM, 10/24/81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.
James R. Holley (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Holley
P.O. Box 1389, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 1981



Ruth Brack
Notary Public.

My commission expires

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1981

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: 10/17/81
DATE COMPLETED: 10/24/81

Big "J" Prod. & Quadel Energy Corp.
STANDISH No. 1
NE NW SE
Sec. 32, Twp. 22S, Rge. 14W,
Stafford County, KS

ELEVATION: G.L.
K.B.

FORMATION DATA:

not available

SURFACE DATA:

Ran 8 jts. 28# used 8-5/8"
casing; tally: 309'
Set @ 316' w/225 sks com.,
2% gel, 3% cc., cement circ.,
plug down 11 PM, 10/17/81
By Sun

PLUGGING DATA:

60 sks @ 630'
40 sks @ 300'
10 sks @ 40'
10 sks in rathole; by Sun
50/50 poz., 2% gel, 3% cc.,
Plug down 4:30 PM, 10/24/81
Orders by J. H. Metz

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

James R. Holley, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

James R. Holley

Subscribed and Sworn to before me this 30th day of October 1981.
Ruth Brack

Notary Public

Subscribed and Sworn to before me this

30th day of October 1981.



RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1981

CONSERVATION DIVISION
Wichita, Kansas