


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 23 Twp. 22S Rge. 15 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
NW SE SW

Lease Owner Alpine Drilling Co., Inc.  
Lease Name Miller Well No. 1-A  
Office Address 800 Bitting Bldg., Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed January 24 1979  
Application for plugging filed January 24 1979  
Application for plugging approved January 24 1979  
Plugging commenced January 24 1979  
Plugging completed January 24 1979  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4045  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged as follows: Filled hole w/mud, spotted 50 sx 50/50 pozmix 2% gel thru D.P. @ 420'; mud to 240', spotted 25 sx, mud to 40', 1 sx hulls & wood plug for solid bridge, 10 sx to base of cellar, 2 sx in rathole, complete @ 11 a.m. 1-24-79 by Allied. RECEIVED  
Witness: Leo Massey State Plugger - Hays, Kansas STATE CORPORATION COMMISSION  
Gary Bagby

JAN 26 1979

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet) Hays, Kansas

Name of Plugging Contractor Husky Drilling Co., Inc. 1-26-79

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jon T. Williams, Jr. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

800 Bitting Building, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1979

Geraldine Stewart  
Geraldine Stewart Notary Public.

My commission expires January 12, 1981





800 Bitting Bldg  
Wichita, Kansas 67202  
Phone 316 - 263-7904  
Mobile Phone 316 - 793-7859 Unit 7070

January 24, 1979

WELL LOG- - - - - Miller No. 1-A  
Located: NW SE SW of Sec. 23-22S-15W, Pawnee County, Kansas

OWNER: Alpine Drilling Co., Inc.  
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: 1-17-79  
COMPLETED: 1-24-79

Rotary Total Depth: 4045'

Log

Casing Record

0 - 293 Soil sand & shale  
293 - 398 Shale  
398 - 462 Sand  
462 - 931 Shale & sand  
931 - 960 Anhydrite  
960 - 1660 Shale & Red Bed  
1660 - 1970 Shale & shells  
1970 - 3825 Shale & lime  
3825 - 3938 Lime  
3938 - 4045 Chert

Run 8 jts., 8-5/8", 28#, 8V, Rge  
2&3 used csg., tallied 283.78 se  
@ 290 KB w/250 sx common, 2% gel,  
3% cc, plug down @ 10 p.m.  
1-17-79 by Allied.

Dry & Abandoned - Plugged  
1-24-79

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1979

CONSERVATION DIVISION  
Wichita, Kansas