

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01305-00-00

Spot: NENENESW

Sec/Twnshp/Rge: 13-24S-12E

2500 feet from S Section Line, 2780 feet from E Section Line

Lease Name: GEIST

Well #: 2

County: GREENWOOD

Total Vertical Depth: 1728 feet

Operator License No.: 5394

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	1704		75 SX
SURF	8.25	1287		75 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/21/2016 9:00 AM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DWAIN STOUT

Company:

Phone: (316) 640-9072

Proposed Pump gel from TD to casing. Set a 50 ft. cement plug on bottom of casing. Pump gel to 700 ft. Set a 50 ft. cement plug.
Plugging Pump gel to 250 ft. Cement from 250 ft. to surface. Run 250 ft. of 1" tubing between surface and production casings and
Method: cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/21/2016 1:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1720', pumped 20 sxs cement, pulled tubing to 800', pumped 20 sxs cement, pulled tubing to 150', pumped 170 sxs cement to surface, ran 1" tubing down back side of casing, pumped 55 sxs cement to surface, gel spacers between cement plugs. casing shot @ 800' & 150'.

RECEIVED
KCC DIST # 3

JAN 03

CHANUTE, KS

RECEIVED
KCC DIST # 3

JAN 03 2017

CHANUTE, KS


mtt

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

KCC WICHITA

JAN 06 2017

RECEIVED

Form CP-2/3

INVOICED

JAN 17 2017

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



15-073-01305-00 00
Cement or Acid Field Report
Ticket No. **3093**
Foreman Kevin McCoy
Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
12-21-16	1046	Guest #2	13	24	12	Gw	Ks
Customer <u>R.R.A. INC.</u>			Unit #		Driver		
Mailing Address <u>100 S. MAIN ST. STE 510</u>			104		ALAN M.		
City <u>Wichita</u>			112		DAVE G.		
State <u>Ks</u>			145		STEVE M.		
Zip Code <u>67202</u>							

Job Type P.T.A. old well Hole Depth 1728' Slurry Vol. 66 BBL Tubing 2" x 1"
Casing Depth 1704' Hole Size N/A Slurry Wt. 13.94 Drill Pipe _____
Casing Size & Wt. 7" Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: RAN 2" Tubing inside 7" to 1720'. Spot Cement Plugs As Following.

20 SKS @ 1720'

Gel SPACER

20 SKS @ 800'

Gel SPACER

170 SKS From 150' to SURFACE (ON ID OF 7" & Between 7" & 8")

RAN 1" Tubing down ANNULUS OF 8" to 50' Could not wash down ANY further, MIXED 55 SKS Cement, Good Cement to SURFACE. Shut down, PULL 1" Tubing. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	20	Mileage	3.95	79.00
C 203	265 SKS	60/40 Pozmix Cement	12.75	3378.75
C 206	910 "	Gel 4%	.20 "	182.00
C 206	750 "	Gel SPACER	.20 "	150.00
C 214	40 "	Hulls	.45 "	18.00
C 108 A	11.40 Tons	Ton Mileage	M/C	345.00
C 113	3 HRS	80 BBL VAC TRUCK	85.00	255.00
C 224	3300 gals	City water	10.00 /1000	33.00
KCC WICHITA				
JAN 06 2017				
RECEIVED				
THANK You			Sub TOTAL	5190.75
—M—			Less 5%	279.00
7.5%			Sales Tax	389.31
Authorization <u>witnessed By DWAIN STOUT</u> Title _____			Total	5301.06

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.