

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20330-00-00
Spot: NWSESE Sec/Twshp/Rge: 15-10S-19W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: NUTSCH A Well #: 2
County: ROOKS Total Vertical Depth: 3718 feet

Operator License No.: 34888
Op Name: AMERICAN OIL LLC
Address: 1023 RESERVATION RD.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3715		
PROD	5.5	3716		125 SX
SURF	8.875	220		150 SX
SURF	8.625	250		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2016 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ZACH PATTERSON Company: _____ Phone: (785) 259-3717

Proposed Plugging Method: Past Operator left tubing & rods in bottom of hole, worked on several days to remove from wellbore, unable to get below 1324'. Order out 425 sx 60/40 poz mix 4% gel w/ 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2016 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing and tagged debris at 1324' pulled tubing to 1322' and pumped 180 sx 60/40 poz mix 4% gel, cement circulated. Pulled tubing out of hole and tied onto 5 1/2 casing and pumped 135 sx cement and circulated cement out of backside, shut in backside and pumped 25 sx cement.

Perfs:

Top	Bot	Thru	Comments
3716	3718		

KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: TUBING AND RODS LEFT IN HOLE SINCE 1997 BY PRIOR OPERATOR TOTAL DEPTH UNKNOWN.

Plugged through: TBG

District: 04

Signed

Richard Williams
(TECHNICIAN)

CH

INVOICED Form CP-2/3

JAN 17 2017