

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23024-00-00
Spot: SESE Sec/Twnshp/Rge: 36-8S-17W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: HRABE TED Well #: 6
County: ROOKS Total Vertical Depth: 3420 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 WRD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3418		100 SX
SURF	8.625	216		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2016 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN, WILLIAM F. DBA THE Phone: (785) 885-4850

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 300 # hulls and 7 sx gel.
DV tool at 1268' w/325 sx cement.
PBTD - 2933'.
Perforations: 3078' - 3304.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2016 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Bowman ran in hole with tubing to 2900'. Quality rigged to tubing and pumped 7 sx gel followed by 50 sx cement w/100 # hulls mixed in. Pulled tubing to 1800'. Quality rigged to tubing and pumped 180 sx cement w/200 # hulls mixed in to circulate cement to pit area. Pulled tubing. Topped off 5 1/2" casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" surface casing and pumped 5 sx cement pressured to 200 psi. Shut in pressure 200 psi.

GPS: 39.30924 -099.16005

Perfs:


Top	Bot	Thru	Comments
3304			
3283			
3276			
3257			
3200			
3190			
3160			
3135			
3104			
3078	3304		

KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: QUALITY OIL WELL CEMENTING CO TICKET # 7310

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

INVOICED
JAN 19 2017 Form CP-2/3

DEC 29 2016