

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-20165-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 1-32S-10E  
3890 feet from S Section Line, 4981 feet from E Section Line  
Lease Name: OLIVER Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 2282 feet

Operator License No.: 3591  
Op Name: C & E OIL, LLC  
Address: 422 ELM  
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2250		0 SX
SURF	8.625	40		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2016 12:00 AM  
Plug Co. License No.: 3591 Plug Co. Name: C & E OIL, LLC  
Proposal Rcvd. from: ED TRIBOULET Company: \_\_\_\_\_ Phone: (620) 647-3601

Proposed Plugging Method: Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/11/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2200' gelled hole and spotted 15 sack plug. Pulled 1" and perforated casing at 1100' and 550'. Ran back into 1100' and spotted 15 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 151 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1975	1990		


RECEIVED  
KCC DIST # 3  
JAN 10 2017  
CHANUTE, KS  
DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JAN 13 2017

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

JAN 19 2017

Form CP-2/3