

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22312-00-00
Spot: SESWSSEW Sec/Twnshp/Rge: 14-14S-21W
120 feet from S Section Line, 1710 feet from W Section Line
Lease Name: STALNAKER-DINKEL Well #: 1-14
County: TREGO Total Vertical Depth: 4090 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 4084 | | 150 SX |
| SURF | 8.625 | 222 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2016 9:00 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING-NELSON OIL CO INC Phone: (785) 621-2610

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/650 # hulls and 16 sx gel.
Port collar at 1544' w/140 sx cement.
Perforations: 3616' - 3618', 3916' - 3922' and 3970' - 3972'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2016 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3963' and pumped 16 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 1650' and pumped 160 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 20 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 150 psi.

GPS: 38.82710 -099.62708

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3970 | 3972 | | |
| 3916 | 3922 | | |
| 3616 | 3618 | | |
| 3132 | 3135 | | |

KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2806

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

JAN 19 2017

Form CP-2/3

DEC 27 2016