

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-02619-00-00
Spot: SWSWSWNW Sec/Twnshp/Rge: 10-14S-14W
2936 feet from S Section Line, 4996 feet from E Section Line
Lease Name: SOLOMON BOXBERGER Well #: 3
County: RUSSELL Total Vertical Depth: 3247 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3247		200 SX
SURF	8.625	535		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/13/2016 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY E&P, LLC DBA Phone: (620) 617-0603

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 9 sx gel.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/13/2016 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1400'. Had squeezed at 600' and cement circulated. Ran tubing to 3030' and pumped 8 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 1446' and pumped 75 sx cement w/ 100 # hulls. Pulled tubing to 686' and pumped 75 sx cement. Cement circulated to the pit. POOH. Topped off with 15 sx cement. Hole standing full. Braden head was dug up and found to be full of cement.

GPS: 38.84995 -098.8720

Perfs:

Top	Bot	Thru	Comments
3247	3255		
3157	3162		
3076	3080		
3044	3050		
3030	3034		
3013	3017		
2990	2998		
2891	2900		
2809	2811		
2798	2801		
2702	2706		

KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENTING TICKET # 44416

Plugged through: TBG

District: 04

Signed _____

Ray Dinkel

(TECHNICIAN)

CM

DEC 16 2016

INVOICED
JAN 19 2017

Form CP-2/3