

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20767-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 10-12S-21W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ELSIE A Well #: 10
County: TREGO Total Vertical Depth: 4093 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4070		225 SX
SURF	8.625	245		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2016 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DALLAS PRESTON Company: EDISON OPERATING COMPANY L Phone: (620) 886-0612

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3422' - 3427', 3952' - 3962' and 4001' - 4014'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2016 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2270', 1775' and 1000'. Ran tubing to 3900' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 3190' and pumped 100 sx cement. Pulled tubing to 2240' and pumped 100 sx cement. Pulled tubing to 1290' and pumped 135 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 40 sx cement. Cement fell. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 200 psi.
12/16/2016 - Topped off casing with 50 sx cement. Hole standing full.

GPS: 39.02182 -099.64838

Perfs:

Top	Bot	Thru	Comments
4001	4014		
3952	3962		
3422	3427		


KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENT TICKET # 44477 AND 44418

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

JAN 19 2017

cm

DEC 27 2016