

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23933-00-00  
Spot: N2SESWNE Sec/Twnshp/Rge: 7-10S-25W  
2170 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: BETTY WERTH Well #: 4  
County: GRAHAM Total Vertical Depth: 4074 feet

Operator License No.: 34117  
Op Name: ETERNITY EXPLORATION, LLC  
Address: 338 SPYGLASS DR  
COPPELL, TX 75019

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4069		175 sx
SURF	8.625	218		475 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/16/2016 11:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BUTCH DRYLIE Company: ETERNITY EXPLORATION, LLC D Phone: (785) 650-4404

Proposed Plugging Method: Ordered 410 sx 60/40 pozmix 4% gel cement w/300 # hulls and 13 sx gel.  
DV Tool at 2150' w/420 sx cement.  
Perforations: 3828' - 3832', 3922' - 3926' and 3966' - 3970'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/16/2016 4:30 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 3930' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2190' and pumped 100 sx cement. Pulled tubing to 1193' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 15 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 150 psi.

GPS: 39.19850 -100.15113

**Perfs:**

Top	Bot	Thru	Comments
3966	3970		
3922	3926		
3828	3832		

KCC WICHITA  
JAN 09 2017  
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2793

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN) INVOICED CM

JAN 19 2017

Form CP-2/3

DEC 27 2016