

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-30225-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 26-18S-15W  
3626 feet from S Section Line, 335 feet from E Section Line  
Lease Name: BAHR A Well #: 1  
County: BARTON Total Vertical Depth: 3601 feet

Operator License No.: 3273  
Op. Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3601		175 SX
SURF	8.625	939		475 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/09/2016 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L. LOEB, LLC DBA Phone: (719) 340-8985

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/09/2016 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 950'. Ran tubing to 3450'. Tied to tubing and pumped 125 sx cement w/300 # hulls. Pulled tubing to 2200'. Tied to tubing and pumped 10 sx gel. Pulled tubing to 1350'. Tied to tubing and pumped 70 sx cement w/100 # hulls. Pulled tubing to 700'. Circulated cement to surface with 225 sx cement on casing and surface pipe. Pulled tubing and topped off with 5 sx cement.  
12/12/2016- Topped off with 13 sx cement.  
GPS: 38.45708 -098.94205

Perfs:

Top	Bot	Thru	Comments
3559	3562		
3535	3550		
3516	3526		

KCC WICHITA  
JAN 09 2017  
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) C M

DEC 16 2016

INVOICED Form CP-2/3  
JAN 19 2017