

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-20032-00-01  
Spot: SWSE Sec/Twnshp/Rge: 18-25S-4W  
651 feet from S Section Line, 1967 feet from E Section Line  
Lease Name: HILDA WEICHMAN Well #: 1  
County: RENO Total Vertical Depth: 3577 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3557	1675	200 SX
SURF	8.625	248		240 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2016 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TRACY BLACK Company: HERMAN LOEB Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/08/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SAND OFF BOTTOM TO 3480', CAPPED WITH 5 SX CEMENT. CUT CASING OFF @ 1675' PULLED TO 750' SPOTTED PLUG WITH 50 SX CEMENT 3% CC AND LET SET 1.5 HR. TAGGED @ 410'. PULLED CASING TO 350' CIRCULATED TO SURFACE WITH 155 SX CEMENT W 3% CC AND 100# HULLS.

Perfs:

Top	Bot	Thru	Comments
3545	3560		

Remarks: COPELAND OUT OF GREAT BEND, TICKET #44413

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)

Form CP-2/3

INVOICED  
JAN 19 2017