

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-01904-00-00  
Spot: NWNESENW Sec/Twnshp/Rge: 19-25S-4W  
3639 feet from S Section Line, 2995 feet from E Section Line  
Lease Name: VALDOIS Well #: 1  
County: RENO Total Vertical Depth: 4001 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4001	1856	200 SX
SURF	10.75	216		200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/08/2016 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: TRACY BLACK Company: HERMAN LOEB Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/09/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3540' WITH 2 SX CEMENT ON TOP. CUT CASING OFF @ 1856', PULLED CASING TO 722'. SPOTTED PLUG WITH 50 SX CEMENT 3% CC., SET 1.5 HR AND TAGGED @ 476'. PULLED CASING TO 410'. CIRCULATED TO SURFACE WITH 245 SX CEMENT WITH 100# HULLS.

Perfs:

Top	Bot	Thru	Comments
3619	3625		

Remarks: COPLAND OUT OF GREAT BEND, TICKET #42145

Plugged through: CSG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

INVOICED Form CP-2/3  
JAN 19 2017

*1/2*