

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-25823-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 11-35S-11E  
5137 feet from S Section Line, 4832 feet from E Section Line  
Lease Name: NEWCOMB Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 1681 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1194		0 SX
SURF	8.625	40		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/29/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Found old plugging record from August 31, 1995. Consolidated hooked onto casing and pumped 2 barrels of cement, followed by 12.5 barrels of gel, followed by 4 barrels of cement. Pumped down well until pressure came up on well. Well was shut in. Well was never cut off. On November 29, 2016 I had Kansas Energy run down well to verify cement. They ran 1" to 360' and tagged cement. Circulated cement to surface. Pulled 1" and topped well off. 37 sacks of cement were used to finish plugging this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
918	932		

RECEIVED  
KCC DIST # 3  
JAN 10 2017  
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through:

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JAN 13 2017

CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
JAN 19 2017

Form CP-2/3