

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-25882-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 2-35S-11E
223 feet from S Section Line, 4849 feet from E Section Line
Lease Name: SMITH Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 1210 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1205		0 SX
SURF	8.625	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 11/28/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:
Ran 1" to 920' gelled hole and spotted 5 sack plug. Pulled up to 600' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 48 sacks of cement were used to plug this well. Well was not cut off per landowners request. He was using in for a guide wire for his TV antenna and bird house.

Perfs:

Top	Bot	Thru	Comments
918	932		

RECEIVED
KCC DIST #3
JAN 10 2017
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.
Plugged through: TBG

District: 03 Signed [Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JAN 13 2017
CONSERVATION DIVISION
WICHITA, KS

INVOICED
JAN 19 2017