

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-25931-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 11-35S-11E  
4266 feet from S Section Line, 4040 feet from E Section Line  
Lease Name: REXROAD Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 1223 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1223		0 SX
SURF	8.625	40		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/29/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 980' gelled hole and spotted 5 sack plug. Pulled up to 600' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 50 sacks of cement were used to plug this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
1091'	1100'		


RECEIVED  
KCC DIST # 3  
JAN 10 2017  
CHANUTE, KS  
DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JAN 13 2017

CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
JAN 19 2017

Form CP-2/3