

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-02959-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 27-33S-14E
226 feet from S Section Line, 2037 feet from E Section Line
Lease Name: EDDS Well #: OW-1
County: MONTGOMERY Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	750		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 350'. Run 1" back in and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 11/23/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 480' and hit solid. Gelled hole and spotted 4 sack plug. Pulled 1" and perforated casing at 225'. Ran 1" back into 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 1-10 sacks of cement were used to plug this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
700	710		

RECEIVED
KCC DIST #3
JAN 10 2017
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 13 2017

CONSERVATION DIVISION
WICHITA, KS

INVOICED

JAN 19 2017

Form CP-2/3