

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-29339-00-00

Spot: SWNWSE

Sec/Twnshp/Rge: 27-33S-14E

1525 feet from S Section Line, 2496 feet from E Section Line

Lease Name: GULLICK

Well #: M-1

County: MONTGOMERY

Total Vertical Depth: 1229 feet

Operator License No.: 32255

Op Name: KANSAS ENERGY COMPANY, L.L.C.

Address: BOX 68

SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1200		0 SX
SURF	7	20		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/16/2016 12:00 AM

Plug Co: License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: P.J. BUCK

Company:

Phone: (620) 725-3636

Proposed
Plugging
Method:

Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

Witness Type: PARTIAL

Date/Time Plugging Completed: 11/17/2016 12:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 730' gelled hole and spotted 2 sack plug. Pulled up to 500' and spotted 2 sack plug. Pulled up to 225' and tried to circulate cement to surface. Could not get circulation. Pulled 1". Came back next day and tagged cement with 1". Circulated cement to surface. Pulled 1" and topped well off. A total of 12 sacks of cement were used to plug this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
1176	1188		
RECEIVED KCC DIST #3 JAN 10 2017 CHANUTE, KS DS			

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 13 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

INVOICED
JAN 19 2017