

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-32149-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 4-33S-14E
4638 feet from S Section Line, 4671 feet from E Section Line
Lease Name: NORTH JANZEN Well #: 1-A
County: MONTGOMERY Total Vertical Depth: 1225 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1187		80 SX
SURF	8.625	20		7 SX
T1	2.375	1165		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 12/06/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1140' gelled hole and spotted 5 sack plug. Pulled up to 600' and spotted 5 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 35 sacks of cement were used to plug this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
1167	1173		


RECEIVED
KCC DIST #3
JAN 10 2017
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 13 2017

CONSERVATION DIVISION
WICHITA, KS

INVOICED

JAN 19 2017

Form CP-2/3