

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24731-00-00
Spot: E2NE Sec/Twnshp/Rge: 19-20S-11W
1320 feet from N Section Line, 760 feet from E Section Line
Lease Name: SPECE Well #: 1
County: BARTON Total Vertical Depth: 3347 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3339	1560	100 SX
SURF	8.625	306		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2016 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/ 400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1560'. Pulled casing to 1250' and pumped 100 sx cement w/200 # hulls. Pulled casing to 800' and pumped 50 sx cement w/100 # hulls. Pulled casing to 550' and pumped 50 sx cement w/100 # hulls. Pulled casing to 250'. Circulated cement to surface with 100 sx cement. Pulled casing and hole stayed full.

GPS: 38.30077 -098.57430

Perfs:

Top	Bot	Thru	Comments
3331	3339		

KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: BASIC CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

INVOICED

CM

JAN 19 2017

Form CP-2/3

DEC 27 2016