

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-26005-00-00  
Spot: E2SWSWNE Sec/Twnshp/Rge: 35-17S-11W  
2310 feet from N Section Line, 2169 feet from E Section Line  
Lease Name: BRADLEY TRUST Well #: 1-35  
County: BARTON Total Vertical Depth: 3400 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3397	2000	230 SX
SURF	8.625	364		300 SX
TI	2.875	3379		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2016 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Set CIBP at 3000' and 3290'. Cut casing at 2000'. Pulled casing to 1300' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 650' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 100 sx cement. Pulled casing and hole stayed full.

GPS: 38.43604 -098.51605

Perfs:

KCC WICHITA  
JAN 09 2017  
RECEIVED

Remarks: BASIC CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

INVOICED  
JAN 19 2017

Form CP-2/3

DEC 27 2016