

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22092-00-00
Spot: SWNENW Sec/Twnshp/Rge: 26-30S-8E
4513 feet from S Section Line, 3411 feet from E Section Line
Lease Name: SLEEPER Well #: B-5
County: ELK Total Vertical Depth: 2550 feet

Operator License No.: 4699
Op Name: PHILLIPS OIL PROPERTIES INC.
Address: 733 N. BALTIMORE
DERBY, KS 67037

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2028		75 SX
SURF	8.625	457		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: TROY A. PHILLIPS Company: _____ Phone: (316) 295-4335

Proposed Plugging Method: Cement plug at 1850, cement plug at 1000' perforate at 500' and circulate cement to surface

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 10/10/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1850' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Ran 1" back into 1000' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 230 sacks of cement were used to plug this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
1940	1944		
1882	1886		

RECEIVED
KCC DIST #3
JAN 10 2017
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST.

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JAN 13 2017
CONSERVATION DIVISION
WICHITA, KS

INVOICED
JAN 19 2017