

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-22123-00-00  
Spot: SENENW Sec/Twnshp/Rge: 26-30S-8E  
4277 feet from S Section Line, 3177 feet from E Section Line  
Lease Name: SLEEPER Well #: B-7  
County: ELK Total Vertical Depth: 2550 feet

Operator License No.: 4699  
Op Name: PHILLIPS OIL PROPERTIES INC.  
Address: 733 N. BALTIMORE  
DERBY, KS 67037

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2009		75 SX
SURF	8.625	456		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: TROY A. PHILLIPS Company: \_\_\_\_\_ Phone: (316) 295-4335

Proposed Plugging Method: Cement plug at 1825', cement plug at 1000' perforate 500' and circulate cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/04/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1825' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Ran 1" back into 1000' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 235 sacks of cement were used to plug this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
1940	1948		
1890	1895		
1836	1842		

RECEIVED  
KCC DIST #3  
JAN 10 2017  
CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JAN 13 2017

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

Form CP-2/3

JAN 19 2017