

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty Company, Inc.
 Complete Address: 800 Bitting Bldg., Wichita, Kansas
 Lease Name Wright Well No. # 1
 Location SE SW NE Sec. 35 Twp. 22 Rge. 14 (E) (W) W
 County Stafford Total Depth 3850'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Glen & Smith Casing Pulling Company
 Address: Box 156, Ellinwood, Kansas License No. 396
 Operation Completed: Hour 11:30AM Day 16th Month Nov. Year 1965

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cement circulated. 3847' of 5 1/2" long string,
cemented with 125 sacks. Plug back to 3834'. Top perforation 3587'. Bottom
of the hole was sanded to 3575', and cemented with 5 sacks. 3293' of 5 1/2" long
string was recovered from the hole. Fluid was up in the hole. Bridge plug was
pushed in fluid to 240', rock bridge from 240' to 230', 8 sacks of cement was
mixed in a barrel, and put on plug at 230', through the dump bailer, and let
set over-night. Next morning hole was bailed dry, and 17 sacks of cement was
added to the plug. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/17/65
INV. NO. 2196-4