

13.081.1013.00.00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1963

11-1-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150 Mc Pherson, Kansas

Lease Name Correll Gas Unit. Well No. 1

Location C SE NE Sec. 8 Twp. 30 Rge. 33 (E) (W)

County Haskell Total Depth 4875'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Service

Address: Chase, Kansas License No. 436

Operation Completed: Hour 10 AM Day 30 Month 10 Year 63

The Above well was plugged as follows:

8 5/8"-768' Circulated w/cement. 5 1/2"-4875' Cemented. Perforations 4800'

Plug bottom w/15 Sax.cement 4875' to 4770' Mud 4770' to 700'

35 Sax.cement 700' to 600' Mud 600' to 50'

Rock bridge 50' to 40' 15 Sax.cement 40' to 0

Pulled 1775' 5 1/2" pipe. Company pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11-1-63

INV. NO. 88003-W