

State of Kansas



15.081.30079.00.00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ley of Mallonee-Coppinger Oper. has this
date requested permission to plug the following described well:

Mr. Ley guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Coppinger Operations Inc.

Complete Address: 1207 Union National Building, Wichita, Kansas

Lease Name: Rooney Well No. 2

Location: C NW NW Sec. 5 Twp. 30 Rge. 34 (E) (W)

County Haskell Total Depth 5740' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ley was instructed to plug the well as follows:

8 5/8" to 809' circulated w/ cement. T.D. 5740'

Mud 5740' to 700' Spot 35 sacks cement 700' to 600'

Mud 600' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Weld Plate on 8 5/8". Pump.

Very truly yours,

Edward J. Eves
Conservation Division Agent