



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Waston of Frank J. Black has this
 date requested permission to plug the following described well:

Mr. Waston guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: Box 150 Mc Pherson, Kansas

Lease Name: M.H. Williams Well No. 2

Location: NW SW Sec. 7 Twp. 30 Rge. 33 (E)(W)

County Haskell Total Depth 4850' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Waston was instructed to plug the well as follows:

8 5/8"-741' Circulated w/cement. 5 1/2"-4849' Cemented.

Plug bottom w/sand and 15 Sax. cement 4850' to 4750' Mid 4750' to 700'

35 Sax. cement 700' to 600' Mid 600' to 50'

Rock bridge 50' to 40' 15 Sax. cement 40' to surface.

Very truly yours,

[Signature]
 Conservation Division Agent