

State of Kansas



15-145-20445-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

STATE CORPORATION COMMISSION

MAR 22 1977

CONSERVATION DIVISION
Wichita, Kansas

3-22-77

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Towns of Abercrombie Drlg. has this date requested permission to plug the following described well:

Mr. Towns guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg., Inc.

Complete Address: 801 Union Center, Wichita, Ks.

Lease Name: Wesley Well No. 1

Location: NE NW SE Sec. 11 Twp. 22 Rge. (E)(W) 15

County: Pawnee Total Depth 3970' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Towns was instructed to plug the well as follows:

 Gun pits, circulate heavy mud, set 50 sk cmt plug at 420' thru drill

 pipe. Heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy

 mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

 R. W. Massey
Conservation Division Agent