



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B & B Drlg. has this date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Co.

Complete Address: 603 Union Center Wichita, Kansas

Lease Name: Branstetter Well No. 1

Location: NE NW NW Sec. 11 Twp. 22 Rge. (E)(W) 15

County: Pawnee Total Depth 3958' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 450' and displace
50 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. R. Messers
Conservation Division Agent