



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1964

CONSERVATION DIVISION
Wichita, Kansas

3-9-64

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Dale Stromquist of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Stromquist guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Keeley "D" Well No. # 1

Location: SE NE NW Sec. 34 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3740 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stromquist was instructed to plug the well as follows:

258' of 8 5/8" surface pipe, cement circulated. Fill hole
with drilling mud to 250', 1st cementing plug, bridge with
hulls, and cement with 25 sacks. Fill hole with mud to 40',
2nd cementing plug, bridge with hulls, and cement with 10
sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving
Conservation Division Agent