


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 30 Twp 22S Rge. (E) 13W(W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Rocket Drilling Company  
Lease Name Moon Well No. 1  
Office Address 352 North Broadway, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 16, 19 52  
Application for plugging filed October 16, 19 52  
Application for plugging approved October 17, 19 52  
Plugging commenced October 16, 19 52  
Plugging completed October 16, 19 52  
Reason for abandonment of well or producing formation --

If a producing well is abandoned, date of last production -- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas  
Producing formation --- Depth to top -- Bottom -- Total Depth of Well 3940 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	326'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 300'. Set plug and cemented with 20 sacks. Filled hole with mud to 35'. Set plug and cemented with 10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 21 1952

10-21-52

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rocket Drilling Company  
Address 352 North Broadway, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
B. W. Burks (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *B. W. Burks*  
352 North Broadway, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 1952

My commission expires 12-3-55  
*Barbara Newby*  
Notary Public.

PLUGGING  
FILED SEC. 30 T. 22 S. R. 13 W. 1952  
BOOK PAGE 52 LINE 36

**ROCKET DRILLING COMPANY**  
 352 North Broadway  
 Wichita 2, Kansas

Rocket Drilling Company, Etal  
 352 North Broadway  
 Wichita 2, Kansas

#1 Moon  
 SW SW NW; 30-22-13W  
 Stafford County, Kansas

Elevation: 1925 R.B.  
 Spudded: October 6, 1952  
 Rotary Completed: October 16, 1952  
 Cable Tools Completed: None  
 Acid Treatment: None  
 Initial Production: Dry & Abandoned  
 Contractor: Rocket Drilling Company

CASING RECORD

326" 8-5/8" O. D. 24# Seamless Casing Cemented W/175 Sacks Cement.  
 5-1/2" None.

DRILLERS LOG

Sand	0 to 245	Lime	2190 to 2220
Shale	260	Lime & Shale	2365
Sand	295	Shale & Lime	2645
Shale	326	Lime & Shale	2825
Red Bed & Shale	815	Shale & Lime	3025
Anhydrite	840	Lime	3135
Shale & Shells	1030	Shale & Lime	3288
Shale & Salt	1580	Lime & Shale	3383
Lime & Shale	1895	Shale & Shells	3454
Sand	1900	Lime	3765
Lime	2055	Chert	3853
Sand	2087	Simpson Shale	3902
Lime	2180	Lime	3940 TD
Sand	2190		

STATE OF KANSAS) SS:  
 SEDGWICK COUNTY)

**PLUGGING**  
 FILE SEC 30 T 22 R 132  
 BOOK PAGE 52 LINE 36

I hereby certify that to the best of my knowledge and belief, the foregoing log is true and correct.

RECEIVED  
 REGISTRATION COMMISSION  
 OCT 21 1952  
 REGISTRATION DIVISION  
 WICHITA, KANSAS

ROCKET DRILLING COMPANY

By [Signature]

Subscribed and sworn to before me, a Notary Public, in and for the State and County aforesaid this 20th day of October, 1952.

My Commission Expires: 12-3-55

[Signature]  
 Notary Public