

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Gitting Building
Wichita, Kansas

Stafford County. Sec. 30 Twp. 22 Rge. (E) 13 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NE NE
Lease Owner Finston, et al
Lease Name Norris Well No. 1
Office Address 409 Mayo Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-11-50 19
Application for plugging filed 7-11-50 19
Application for plugging approved 7-11-50 19
Plugging commenced 7-11-50 19
Plugging completed 7-11-50 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	349	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 349'. Set plug and 15 sacks cement. Filled with mud to 30'. Set plug tied with steel wire - 10 sacks cement to surface.

8-4-50

AUG 4 - 1950

SEAL OF THE
COMMISSIONER
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Murfin Drilling Co.
Address 910 Union National Bank Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.R. Murfin
910 Union Natl. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of August, 1950.
Lester Hays Notary Public.

My commission expires 3-5-52

PLUGGING
FILE SEC 32 T 22 R 13
BOOK PAGE 15 LINE 46

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Finston, Murfin, et al

SEC. 30 T. 22 R. 13W

FARM Norris

NO. 1

LOC. NE NE NE

TOTAL DEPTH 3950

COUNTY Stafford


COMM. 6-25-50

COMP. 7-11-50

SHOT OR TREATED

CONTRACTOR Murfin Drilling Co.

ISSUED



CASINO

20 10
 15% 8% 350
 12% 6%
 13% 5%

ELEVATION 1905 DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

285 sand-shale		<u>Tops</u>	
315 sand			
524 red bed-shells	Heebner		3313
790 red bed	Dodge		3344
825 anhydrite	Brown Lime		3457
1100 shale-shells	Lans. - K. C.		3475
1270 shale	Base K. C.		3700
1550 salt-shale-shells	Cong.		3799
1600 shale	Viola		3806
1905 lime	Simpson		3858
2045 lime-shale	Arbuckle		3897
2175 lime	T.D.		3950
2965 shale-lime			
3090 lime			
3225 lime-shale			
3375 lime			
3440 lime-shale			
3460 shale			
3760 lime			
3785 lime-shale			
3800 shale			
3865 lime			
3880 shale-sand			
3900 shale			
3935 Arbuckle			
3950 lime			
T.D.			

RECEIVED
 Conservation Div.

AUG 4 - 1950

STATE CORPORATION
 COMMISSION
 KANSAS

STATE OF KANSAS)
) SS:
 SEDGWICK COUNTY)

I, W. R. Murfin, of the Murfin Drilling Company, a partnership, contractor engaged for the drilling of the Norris No. 1 well, located in the NE NE NE of Section 30, Township 22, Range 13 West, Stafford County, Kansas, upon oath state that the above and foregoing is a true and correct copy of the log of said well.

W. R. Murfin
 W. R. Murfin

Subscribed and sworn to before me this 2nd day of August, 1950.

Lesaune Hays
 Notary Public

My Commission Expires: 3-5-52

PLUGGING
 FILE SEC 30 T 22 R 13W
 BOOK PAGE 15 LINE 40