


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 24 Twp. 22S Rge. 13 (E)xx (W)
Location as "NE/CNW%SW%" or footage from lines SW SW SW
Lease Owner John Lindas Oil, Inc.
Lease Name Hitz Well No. 1
Office Address 701 Rule Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 19, 19 54
Application for plugging filed March 19, 19 54
Application for plugging approved March 19, 19 54
Plugging commenced March 19, 19 54
Plugging completed March 19, 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Murial Rizes
Producing formation Depth to top Bottom Total Depth of Well 3791 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	271	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled hole with heavy mud to 270'. Set Plug, with 2 gallons of Hulls in sack on top of plug and 20 sacks cement. Filled hole with mud to 40' and set plug with 2 gallons Hulls on top of plug and 10 sacks cement.

RECEIVED
STATE CORP. COMMISSION
MAR 25 1954
3-25-54
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor John Lindas Oil, Inc.
Address 701 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. M. Gallaway (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. M. Gallaway*
701 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 54
Catherine Hancy
Notary Public.

My commission expires March 25, 1956.



DRILLING LOG

Lease Operator: John Lindas Oil, Inc.
701 Rule Building
Wichita, Kansas

County: Stafford
Location: SW/4 SW/4 SW/4
Section: 24-22S-10W
Elevation: 1884' DF
1881' Gr.

Well: Hits No. 1

Commenced: March 7, 1954
Completed: March 19, 1954
Surface Casing: 275' 8-5/8" casing, 225 sacks
cement and 2 calcium chloride.
Oil String: None

Contractor: John Lindas Oil, Inc.
701 Rule Building
Wichita, Kansas

FIGURES INDICATE BOTTOM OF FORMATION

0	to	276	
276		535	Red Bed
535		720	Shale and Shells
720		755	Anhydrite
755		960	Red Bed and Shells
960		1165	Shale
1165		1580	Shale and Shells
1580		1850	Lime and Shale
1850		2135	Lime
2135		2225	Shale and Lime
2225		2330	Lime
2330		2560	Shale
2560		2755	Shale and Lime
2755		2860	Lime and Shale
2860		3130	Shale and Lime
3130		3180	Lime
3180		3330	Lime
3330		3370	Lime and Shale
3370		3375	Lime (Brown)
3375		3390	Lime and Shale
3390		3400	Lime (Kansas City)
3400		3600	Lime
3600		3710	Lime and Shale
3710		3728	Lime
3728		3750	Shale
3750		3785	Shale and Sand (Simpson)
3785		3791	Arbuckle
		3791	Total Depth

RECEIVED

STATE COMMISSION

MAR 25 1954

CONSERVATION DIVISION

STATE OF KANSAS)
 : ss
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, depose and state that the above statement and log is a true and correct record of the well drilled by John Lindas Oil, Inc., at the location above described.

F. W. Callaway
F. W. Callaway

Subscribed and sworn to before me this 24th day of March, 1954.

Catherine Dancy
Notary Public

My Commission Expires: March 25, 1956.

PLUGGING
FILE SEC 24 T 22 S 13 W
BOOK PAGE 2 LINE 23