


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 4 Twp. 22 Rge. 11 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$  NE $\frac{1}{4}$  SW $\frac{1}{4}$   
Lease Owner Republic Natural Gas Company  
Lease Name Fair "B" Well No. 3  
Office Address Box 126, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed June 20 1954  
Application for plugging filed June 25 1954  
Application for plugging approved Verbal approval from M. A. Rives 6-20-1954  
Plugging commenced June 20 1954  
Plugging completed June 20 1954  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 3560 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	189'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3560 - 185 Rotary mud  
185 Bridge plug with 1/4 sack of hulls on top.  
185 - 115 35 sacks cement  
115 - 30 Mud  
30 Bridge plug with 1/2 sacks of hulls on top.  
30 - surface 15 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Drilling Company  
Address 507 Orpheum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, SS.  
P. B. Horst (employee of owner) or (owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


6-26-54

(Signature) P. B. Horst

Box 126, Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1954.

My commission expires 8-20-55 Notary Public.



GABBERT-JONES DRILLING COMPANY  
WICHITA, KANSAS  
DRILLERS WELL LOG

FAIR #B-3  
 SE NE SW, Sec. 4-22-11W  
 STAFFORD COUNTY, KANSAS  
 COMMENCED 6-8-54  
 COMPLETED 6-20-54

DEPTH		FORMATION	REMARKS
FROM	TO		
0	20	SAND	
20	80	SHALE & SHELLS	
80	190	RED BED	RAN 193.80' OF 10 3/4 CASING, CEMENTED @ 190' w/150 SACKS CEMENT.
190	365	RED BED	
365	1180	SHALE	
1180	1290	SHALE & SALT	
1290	1425	SHALE & SHELLS	
1425	1520	LIME	
1520	1580	CHERTY LIME	
1580	1665	SHALE & SHELLS	
1665	1855	SHALE & LIME	
1855	1990	LIME	
1990	2405	SHALE & SHELLS	
2405	2595	SHALE & LIME	
2595	2805	BROKEN LIME	
2805	2935	LIME & SHALE	
2935	3010	LIME	
3010	3155	BROKEN LIME	
3155	3220	KANSAS CITY LIME	
3220	3385	LIME	
3385	3530	CHERT & LIME	
3530	3559	CHERT & ARBUCKLE LIME	
3559	TD		D. & A. ABANDONED

EXECUTED THIS 24TH DAY OF JUNE, 1954

C. L. Gabbert

STATE OF KANSAS }  
 COUNTY OF SEDGWICK) 89

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 24 DAY OF June, 1954 PERSONALLY APPEARED C. L. Gabbert TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES My commission expires Mar. 28, 1957

Mar. Reser  
 NOTARY PUBLIC

**PLUGGING**  
 JUN 20 1954  
 CONSERVATION DIVISION  
 Wichita, Kansas