

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22576-0000

LEASE NAME Fair B

WELL NUMBER #5

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 4 TWP. 225 RGE. 11 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 8/11/03

Plugging Completed 8/12/03

AUG 21 2003

KCC WICHITA

LEASE OPERATOR Larson Operating Company

ADDRESS 562 W. Highway 4, Olmitz, KS. 67564-8561

PHONE# (620) 653-7368 OPERATORS LICENSE NO. 3842

Character of Well oil

(Oil), Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on August 11, 2003 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 3342.5 Bottom 3522 T.D. 3600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	304'	8-5/8"	304'	0'
	Production	0'	3573'	5-1/2"	3573'	2613.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Dump sand down well. Waited 2 hrs. Run bailer in-tagged sand @1080'. Pumped down casing. Run bailer in-tagged sand @3230'. Spot 5 sacks cement on bottom. Set jacks and pulled stretch into pipe. Run knife into 2600'-cut 5-1/2" casing. Pulled to 600' - pumped 10 sacks of gel with 200# nuts & 50 sacks cement with 100# nuts. Pulled to 350' - pumped 50 sacks cement. Pulled to 40' - pumped 20 sacks cement. Laid down last joint - tore down and moved off.

Name of Plugging Contractor D. S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS. 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thomas Larson (Larson Operating Company)

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph F. Strube
(Address) _____

SUBSCRIBED AND SWORN TO before me this 20th day of August, 2003

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06
Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06