

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-10840-0002

API NUMBER Compl. 5/54

LEASE NAME FAIR B

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SE-SE-SW
SEC. 4 TWP. 22S RGE. 11 (X) or (W)

COUNTY Stafford

Date Well Completed 5/54

Plugging Commenced 6/5/89

Plugging Completed 6/7/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Quinoco Petroleum, Inc.

ADDRESS P.O. Box 378111, Denver, CO 80237

PHONE#(303) 850-7373 OPERATORS LICENSE NO. 03613

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 1989 (date)

by W.Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached?

Producing Formation L-KC/Arbuckle Depth to Top 3197 Bottom 3841 T.D. 3841

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L-KC	Water	Surf	182	8 5/8"	182	
Arbuckle	Water	Sruf	3696	5 1/2"	3696	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran 94 jts of 23/8" tbg open-ended to 3041' broke circ. Pumped 60 sx 60/40 poz w/ 8% gel.
Pulled 25 jts tbg end of pipe @ 2234'. Pmpd 23 sx gel. Pulled 54 jts tbg end of pipe @ 488' and pumped 50 sx 60/40 poz w/ 8% gel. Cmt circ out 5 1/2" csg. Pulled rest of tbg (15 jts) fill csg w/ 20 sx 60/40 poz, 8% gel to top off csg. Total cmt used to pull well 125sx, 23 sx gel.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P.O. Box 579, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Quinoco Petroleum, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Suzanne E. Meadows (Employee of Operator Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Suzanne E. Meadows

(Address) P.O. Box 378111, Denver, CO 80237

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 89

My Commission Expires: 4/19/93

Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL - 3 1989

CONSERVATION DIVISION