


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 25 Twp. 22 Rge. 12 (E) (W)
Location as "NE/CNW'SW" or footage from lines SW SE NW
Lease Owner: Petroleum, Inc.
Lease Name: Sealy Well No. 1
Office Address: 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
Date well completed: June 22, 19 53
Application for plugging filed: June 22, 19 53
Application for plugging approved: June 22, 19 53
Plugging commenced: June 22, 19 53
Plugging completed: June 22, 19 53
Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Mr. M. A. Rives
Producing formation: Depth to top: Bottom: Total Depth of Well 3670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	204'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 200' and set wooden plug at 200', followed by 1/2 sack hulls and 20 sacks cement displaced through drill pipe. Mudded up to 40' and set second wooden plug followed by 1/2 sack of hulls and 10 sacks cement filling hole to base of well cellar.

RECEIVED
STATE OF KANSAS

7-9-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Garvey Drilling Company
Address: R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W W Fisher

305 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 53

My commission expires October 13, 1954

Charles J. Heidman Notary Public



DRILLER'S LOG SEALY NO. 1

Petroleum, Inc., Operator
Garvey Drilling Company, Contractor

Section 25, Twp. 22S, Rge. 12W

Location: SW SE NW

Drilling Commenced: June 13, 1953
Drilling Completed: June 22, 1953

County: Stafford County, Kansas

R.T.D.: 3670'

Casing Record: 8 5/8" @ 204' w/175 sax

Production: D & A

Figures below indicate bottom of formation:

80	Sand
204	Shale & Red Bed
581	Red Bed & Shale
607	Anhydrite
1440	Shale & Shells
1930	Lime & Shale
2050	Lime
2625	Lime & Shale
2850	Shale & Shells
3290	Lime & Shale
3561	Lime
3605	Chert
3643	Shale & Sand
3670	Lime, Shale & Sand
3670'	R.T.D.

Tops:

Heebner:	3123 (-1281)
Brown Lime:	3259 (-1417)
Lansing:	3284 (-1442)
Arbuckle:	3661 (-1819)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By *W. W. Fisher*

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 3rd day of July, 1953.

Charlotte H. Fisher
 RECEIVED BY Notary Public
 STATE CORPORATION COMMISSION

My commission expires: October 13, 1954.

JUL 9 1953

PLUGGING
 FILE SEC 25 T 22 R 120
 BOOK PAGE 109 LINE 12

CONSERVATION DIVISION
Wichita, Kansas