

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,320-0060

LEASE NAME Heyen "B"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 25 TWP. 22 RGE. 12 (E) or (W)

COUNTY Stafford

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B
Great Bend, Kansas 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Date Well Completed 10-16-85

Character of Well _____

Plugging Commenced 10-16-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-16-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Paul Luthey-Dist. 1 Dodge City, Ks.

Is ACO-1 filed? yes if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3662'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		surf.	261'	8 5/8"	261'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

50 sx. at 3615'

50 sx. at 600' 15 sx. in rat hole--5 sx. in water well

50 sx. at 270'

10 sx. at 40'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Don Popp (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION (Signature) Don Popp

12-23-85

(Address) Don Popp Hoisington, Ks.

DEC 23 1985


SUBSCRIBED AND SWORN TO before me this 18th day of December, 19 85

CONSERVATION DIVISION
Wichita, Kansas

Bessie M. DeWerff
Notary Public

My Commission Expires: 5-20-89

Bessie M. DeWerff



15-185-01304-0000

H. A. HERSHFIELD & CO.

Waité No. 1

SEC. 25 T. 22 R. 12

NW/4 SW/4

County STAFFORD

Total Depth 3691'

Comm. 1-13-1944 Comp. 1-27-1944

Contractor H. M. Williams Drilling Co.


Abandoned 1-28-1944

CASING

10" 215

Figures Indicate Bottom of Formations

Cellar	6	
clay & sand	44	
sand	140	
shale & shells	225	
shale	330	
red bed, shale & shells	1190	
shale & shells	1610	
lime	1890	
lime & shale	2330	
shale & lime shells	2435	
shale & lime	2680	
shale & shells	2805	
lime & shale	2900	
lime	3155	
lime & shale	3295	
shale	3297	Top Kansas City lime 3297
Lime	3539	Base Kansas City lime 3539
Marmaton	3568	Top Marmaton 3539
Conglomerate	3579	Top conglomerate 3568
Viola lime	3615	Top Viola 3579
Simpson	3623	Top Simpson 3615
shale	3643	
shale & lime	3686	
Arbuckle lime	3691	Top Arbuckle lime 3686
Total Depth	3691	



Slight spotted oil stains 3513-17
 " " " " in Arbuckle
 line
 Haliburton drill stem test recovered
 240' of sulphur water in Arbuckle