


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 36 Twp. 22 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner National Cooperative Refinery Association
Lease Name Durham Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 23, 1955
Application for plugging filed August 23, 1955
Application for plugging approved August 24, 1955
Plugging commenced August 23, 1955
Plugging completed August 23, 1955
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled hole with heavy mud. Made up plug container into top of surface casing. Pumped approximately 75 barrels of mud into hole. Pressured up to 200#. Released plug. Mixed and pumped 100 sax of common and pozmix cement into hole and covered with 1/2 barrel of mud.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Brinrich Drilling Company
Address First National Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. R. Sears (C. R. Sears)

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19____
My commission expires June 30, 1958
C. Orville May Notary Public.

PLUGGING
FILE SEC 36 T 22 R 13W
BOOK PAGE 147 LINE 43

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1955
CONSERVATION DIVISION
Wichita, Kansas

NATIONAL COOPERATIVE REFINERY ASSN.

Well: Durham # 1

NW NW SE

Commenced RD: 8-12-55

Sec. 36-22-13

Completed RD: 8-23-55

Stafford County, Kansas

Casing: 258' 8 5/8" OD 25 1/2#

Elevation: 1878 KB

Total Depth: 3840'

Contractor: Brinrich Drlg. Co., Inc.

Strata	Depth	Tops
Surface Soil & Clay	44	Heebner 3229 - 1351
Sand	200	Broken Lime 3366 - 1488
Red Bed	243	Lansing 3382 - 1504
Red Bed	260	Base of Kan. City 3608 - 1730
Red Bed	709	Viola 3688 - 1865
Anhydrate	739	Simpson 3743 - 1865
Shale & Shells	985	Arbuckle 3800 - 1922
Shale & Shells	1035	Total Depth 3840'
Salt & Shells	1205	
Shale & Shells	1395	
Shale & Shells	1520	
Lime & Shale	1650	
Broken Lime	1837	
Broken Lime	2005	
Lime	2105	
Shale & Lime	2380	
Shale & Lime Shells	2600	
Shale & Lime	2775	
Shale & Lime	2935	
Shale & Lime	3095	
Shale & Lime	3165	
Lime	3210	
Lime & Shale	3237	
Shale & Lime	3340	
Lime & Shale	3425	
Lime & Shale	3491	
Lime	3498	
Lime	3520	
Lime	3565	
Lime	3585	
Lime	3622	
Lime	3675	
Chirt, Shale & Lime	3729	
Chirt, Lime & Shale	3748	
Shale, Chirt & Lime	3785	
Lime, Chirt & Lime	3828	
Lime, Chirt & Shale	3840	
Total Depth	3840	

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRINRICH DRILLING COMPANY, INC.
BY

W. S. Brunson
W. S. Brunson, President

Signed and sworn to in my presence this 24th day of August, 1955, by W. S. Brunson, President of the Brinrich Drilling Company, Inc., a Corporation in the State of Kansas.

My commission expires April 12, 1956.

PLUGGING
WELL SEC 36 T 22 R 13 W
BOOK PAGE 144 LINE 43

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1955
CONSERVATION DIVISION
Wichita, Kansas
Leland B. McLaughlin
L. B. McLaughlin - Notary Public